PLUMBING FIXTURE SCHEDULE

MARK	FIXTURE	PIPE SIZE TRAP	WASTE	C.W.	H.W.
P-1	WATER CLOSET	3"or4"	4"	1"	---

REMARKS: WATER CLOSET, FLUSH VALVE, REGULAR.

ZURN MODEL # Z5655 VITREOUS CHINA, 1.6 GPF, HIGH EFFICIENCY ELONGATED RIM, SIPHON ACTION, 1-1/2" TOP SPUD, LOW CONSUMPTION, FLOOR MOUNTED RIM 15" ABOVE FINISHED FLOOR.

ZURN MODEL # ZEMS6000AV-IS AQUASENSE AV EXPOSED FLUSH VALVE, HARDWIRED, AUTOMATIC SENSOR OPERATED, LOW CONSUMPTION 1.6 GPF, DIAPHRAGM TYPE, CHROME PLATED WITH HIGH BACK PRESSURE VACUUM BREAKER.

ZURN MODEL # P6000-HW6 120VAC/7.6VDC HARDWIRED POWER CONVERTER.

ZURN MODEL # 5950 SOLID PLASTIC, WHITE, ELONGATED SEAT WITH OPEN FRONT, EXTENDED BACK AND CHECK HINGE; LESS COVER.

MARK	FIXTURE	PIPE SIZE TRAP	WASTE	C.W.	H.W.
P-2	WATER CLOSET	3"or4"	4"	1"	---

REMARKS: WATER CLOSET, FLUSH VALVE, ADA ACCESSIBLE.

ZURN MODEL # Z5665 VITREOUS CHINA, 1.6 GPF, HIGH EFFICIENCY ELONGATED RIM, SIPHON ACTION 1-1/2" TOP SPUD, LOW CONSUMPTION, FLOOR MOUNTED RIM 17" ABOVE FINISHED FLOOR.

ZURN MODEL # ZEMS6000AV-IS AQUASENSE AV EXPOSED FLUSH VALVE, HARDWIRED, AUTOMATIC SENSOR OPERATED, LOW CONSUMPTION 1.6 GPF, DIAPHRAGM TYPE, CHROME PLATED WITH HIGH BACK PRESSURE VACUUM BREAKER.

ZURN MODEL # P6000-HW6 120VAC/7.6VDC HARDWIRED POWER CONVERTER.

ZURN MODEL # 5950 SOLID PLASTIC, WHITE, ELONGATED SEAT WITH OPEN FRONT, EXTENDED BACK AND CHECK HINGE; LESS COVER.

MARK	FIXTURE	PIPE SIZE TRAP	WASTE	C.W.	H.W.
P-3	URINAL	2"	2"	3/4"	---

REMARKS: URINAL, WALL HUNG, ADA ACCESSIBLE.

ZURN MODEL # Z5750 1.0 GPF, VITREOUS CHINA, HIGH EFFICIENCY WASHOUT FLUSHING ACTION, WITH 3/4" TOP SPUD.

ZURN MODEL # ZEMS8003AV-IS AQUASENSE AV EXPOSED FLUSH VALVE, HARDWIRED, AUTOMATIC SENSOR OPERATED, LOW CONSUMPTION 1.0 GPF, DIAPHRAGM TYPE, CHROME PLATED WITH HIGH BACK PRESSURE VACUUM BREAKER.

ZURN MODEL # P6000-HW6 120VAC/7.6VDC HARDWIRED POWER CONVERTER.

MOUNT WITH LIP AT A MAXIMUM HEIGHT OF 17" ABOVE FINISH FLOOR.

ZURN MODEL # Z1222 FLOOR MOUNTED, CONCEALED URINAL SUPPORT.

MARK	FIXTURE	PIPE SIZE TRAP	WASTE	C.W.	H.W.
P-4	LAVATORY	1-1/2"	2"	1/2"	1/2"

REMARKS: LAVATORY, UNDERMOUNT, ADA ACCESSIBLE.

ZURN MODEL # Z5220 19"x16" VITREOUS CHINA, RIMLESS OVAL DESIGN FOR UNDERMOUNT INSTALLATION AND FRONT OVERFLOW.

ZURN MODEL # Z6915 AQUASENSE HARDWIRED, ELECTRONIC SENSOR FAUCET WITH 1.0 GPM VANDAL RESISTANT AERATOR AND THERMOSTATIC MIXING VALVE FOR MULTIPLE FAUCETS.

ZURN MODEL # HW6 HARDWIRED POWER CONVERTER.

ZURN MODEL # CWB CONNECTOR WIRE FOR HARDWIRE INSTALLATION.

ZURN MODEL # Z8746-PC ADA POLISHED CHROME PLATED BRASS GRID STRAINER.

3/8" CHROME PLATED SUPPLIES WITH STOP.

CHROME PLATED KENTUCKY CODE "P" TRAP.

INSTALL WASTE AND SUPPLY PIPING COVERS (TRUEBRO LAV GUARD 2 OR EQUAL) IN COMPLIANCE WITH ICC/ANSI A117.1-2003 (IF REQUIRED).

MARK	FIXTURE	PIPE SIZE TRAP	WASTE	C.W.	H.W.
P-5	SINK	1-1/2"	2"	1/2"	1/2"

REMARKS: DOUBLE COMPARTMENT, LAY-IN, REGULAR.

JUST MODEL # DL-1829-A-GR, 18"x29"x7-1/2" SELF-RIMMING, 18 GAUGE, STAINLESS STEEL SINK. SUPPLY WITH CENTER DRAINS.

DELTA MODEL # 26C4935 DECK MOUNT, HEAVY DUTY, RIGID/SWIVEL GOOSENECK SPOUT WITH 1.5 GPM VANDAL RESISTANT FLOW CONTROL AERATOR AND 6" WRIST BLADE HANDLES (8" CENTERS).

JUST MODEL # J-35 STAINLESS STEEL CUP STRAINER WITH REMOVABLE BASKET AND CHROME PLATED TAILPIECE, 4" LONG.

3/8" CHROME PLATED SUPPLIES WITH STOP.

CHROME PLATED KENTUCKY CODE "P" TRAP.

MARK	FIXTURE	PIPE SIZE TRAP	WASTE	C.W.	H.W.
P-6	EWC	1-1/2"	2"	1/2"	---

REMARKS: ELECTRIC WATER COOLER - DUAL HEIGHT, BOTTLE FILLING STATION.

ELKAY MODEL # EZSTL8WSLK BI-LEVEL, BARRIER-FREE, VANDAL RESISTANT BUBBLER, WALL MOUNTED WITH WATER FILTER, STAINLESS STEEL FINISH AND BOTTLE FILLING STATION. BOTTLE FILLING STATION SHALL INCLUDE AN ELECTRONIC SENSOR FOR NO-TOUCH ACTIVATION WITH AUTOMATIC 20-SECOND SHUT-OFF TIMER AND BOTTLE COUNTER.

ZURN MODEL # 1225 ELECTRIC WATER COOLER SUPPORT SYSTEM WITH TOP AND BOTTOM PLATES. FLOOR MOUNTED WITH "PRO-SET" UPRIGHTS.

MOUNT LOWEST SPOUT AT A MAXIMUM HEIGHT OF 36" ABOVE FINISHED FLOOR.

MOUNT HIGHEST SPOUT AT A MAXIMUM HEIGHT OF 40" ABOVE FINISHED FLOOR.

MARK	FIXTURE	PIPE SIZE TRAP	WASTE	C.W.	H.W.
P-7	MOP SINK	3"	3"	1/2"	1/2"

REMARKS: MOLDED HIGH DENSITY COMPOSITE MOP SERVICE BASIN.

ZURN MODEL # Z1996 HIGH DENSITY COMPOSITE, MOLDED MOP BASIN, 24"x24"x10" WITH STAINLESS STEEL DOME STRAINER / LINT BASKET AND A PVC DRAIN WITH ADJUSTABLE CAULKING NUT AND GASKET.

OPTIONS TO BE PROVIDED:
- STAINLESS STEEL BUMPER GUARD
- HOSE AND HOSE BRACKET
- MOP HANGER
- STAINLESS STEEL DRAIN
- SERVICE FAUCET-CHROME PLATED BRONZE, WITH VACUUM BREAKER, INTEGRAL STOPS, ADJUSTABLE WALL BRACE, PAIL HOOK, FOUR-ARM HOT AND COLD HANDLES AND 3/4" HOSE THREAD SPOUT.

PLUMBING LEGEND

SYMBOL	DESCRIPTION
——SS——	SANITARY SEWER PIPING
——G——	GAS PIPING
——SD——	STORM DRAIN PIPING
——OSD——	OVERFLOW STORM DRAIN PIPING
——— — ———	COLD WATER PIPING
——— — — ———	HOT WATER PIPING
— — — — — —	VENT PIPING
CO	CLEAN OUT
CCO	COMBINATION TEST TEE / CLEAN OUT
DSN	DOWNSPOUT NOZZLE
ET	THERMAL EXPANSION TANK
FD	FLOOR DRAIN
FRH	FREEZE PROOF ROOF HYDRANT
FWH	FREEZE PROOF WALL HYDRANT
HB	HOSE BIBB
IMB	ICE MAKER OUTLET BOX
ORD	OVERFLOW ROOF DRAIN
POC	POINT OF CONNECTION
TP	TRAP PRIMER
RD	ROOF DRAIN
VTR	VENT THRU ROOF
WH	WATER HEATER
——⊗——	GAS COCK (PLUG VALVE)
——⊣⊢——	UNION
——○——	BALL VALVE
——⋈——	GATE VALVE
——⋈——	PRESSURE REGULATOR

ACCESSIBLE FIXTURE DETAILS

NO SCALE



LAVATORY

NOTE:
INSTALL PLUMBING GUARDS ON PIPING BELOW ACCESSIBLE LAV.



ELEVATION



WATER COOLER



URINAL



PLAN VIEW

NOTE:
WATER CLOSET STYLE MAY VARY

FLOOR MOUNT WATER CLOSET

AGE GROUP (YEARS OLD)	A (INCHES)	B (INCHES)	C (INCHES)	D (INCHES)	E (INCHES) MINIMUM	E (INCHES) MAXIMUM	F (INCHES) MINIMUM	F (INCHES) MAXIMUM
13 AND UP	34 MIN.	36 MAX.	44 MIN.	17 MAX.	17	19	16	18

NOTE:
INSTALL PLUMBING FIXTURES IN ACCORDANCE WITH ADOPTED EDITION OF ICC/ANSI A117.1 ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES.

SPECIALTY ITEMS

MARK	DESCRIPTION	REMARKS
FD-1	FLOOR DRAIN	ZURN MODEL # ZS415 3" TYPE "B" (ROUND TOP) FLOOR DRAIN WITH 5"ø STAINLESS STEEL, VANDAL PROOF STRAINER.
FD-2	FLOOR DRAIN	ZURN MODEL # ZN415 4" TYPE "B" (ROUND TOP) FLOOR DRAIN WITH 6"ø NICKEL BRONZE STRAINER.
CO-1	FLOOR CLEAN OUT	ZURN MODEL # ZS1440-VP LEVEL-TROL ADJUSTABLE FLOOR CLEANOUT, DURA-COATED CAST IRON BODY, WITH GAS AND WATERTIGHT BRONZE TAPERED THREAD PLUG, AND ROUND SCORIATED SECURE STAINLESS STEEL TOP WITH VANDAL-PROOF SCREWS.
CCO-1	COMBINATION CLEAN OUT/TEST TEE	ZURN Z1406 ADJUSTABLE CLEANOUT WITH SPIGOT CONNECTION FOR CAULKING INTO HUB. DURA-COATED CAST IRON BODY WITH GAS AND WATERTIGHT BRONZE PLUG WITH POLISHED BRONZE VANDAL-PROOF TOP.
HB-1	3/4" HOSE BIBB	WOODFORD MODEL # 24 WALL FAUCET WITH KEY HANDLE AND CHROME FINISH. INSTALL HOSE BIBB 18" ABOVE FINISHED FLOOR (UNLESS OTHERWISE NOTED).
HB-2	3/4" HOSE BIBB	WOODFORD MODEL # 24 WALL FAUCET WITH WHEEL HANDLE AND BRASS FINISH. INSTALL HOSE BIBB 48" ABOVE FINISHED FLOOR (UNLESS OTHERWISE NOTED).
FWH-1	FREEZE PROOF WALL HYDRANT	WOODFORD MODEL # B67 AUTOMATIC DRAINING RECESSED-MOUNTED WALL HYDRANT WITH LOOSE TEE KEY OPERATION, BOX, COVER AND STAINLESS STEEL FINISH.
FRH-1	FREEZE PROOF ROOF HYDRANT	WOODFORD MODEL # RHY2-MS COMMERCIAL ROOF HYDRANT SYSTEM WITH DOUBLE CHECK BACKFLOW PREVENTER, CAST IRON HYDRANT SUPPORT, 2" CAST IRON SHIM, CAST IRON UNDER DECK FLANGE, MOUNTING BOLTS, NUTS AND WASHERS.
ET-1	THERMAL EXPANSION TANK	AMTROL MODEL ST-5 THERMAL EXPANSION TANK.
TP-1	TRAP PRIMER	PRECISION PLUMBING PRODUCTS MODEL # PR-500 PRIME-RITE TRAP PRIMER WITH DU-4 (DISTRIBUTION UNIT).
IMB-1	ICE MAKER OUTLET BOX	IPS MODEL # 9700 WATER TITE ICE MAKER OUTLET BOX, CHROME 1/4 TURN ADAPTER BALL VALVE WITH 1/2" COPPER SWEAT CONNECTION.
RD-1	ROOF DRAIN	JAY R. SMITH MODEL # 1010Y 8" DUCO CAST IRON BODY WITH SECONDARY FLASHING CLAMP, UNDERDECK CLAMPS AND GRAVEL STOP WITH CAST IRON DOME.
RD-2	ROOF DRAIN	JAY R. SMITH MODEL # 1010Y 3" DUCO CAST IRON BODY WITH SECONDARY FLASHING CLAMP, UNDERDECK CLAMPS AND GRAVEL STOP WITH CAST IRON DOME.
ORD-1	OVERFLOW ROOF DRAIN	JAY R. SMITH MODEL # 1080Y 8" DUCO CAST IRON BODY, WITH SECONDARY FLASHING CLAMP, UNDERDECK CLAMPS AND GRAVEL STOP, 2" WATER DAM AND CAST IRON DOME.
DSN-1	DOWNSPOUT NOZZLE	JAY R. SMITH MODEL # 1770Y 12" CAST BRONZE BODY AND FLANGE, POLISHED CHROME FINISH WITH STAINLESS STEEL BIRD SCREEN
BFP-1	BACKFLOW PREVENTER	WATTS SERIES 009 - 009QT 1" REDUCED PRESSURE ZONE ASSEMBLY WITH BRONZE STRAINER.

PLUMBING NOTES

1. EACH CONTRACTOR SHALL BE RESPONSIBLE FOR VISITING THE SITE PRIOR TO BIDDING IN ORDER TO BECOME FAMILIAR WITH THE EXISTING CONDITIONS. ANY DISCREPANCIES OR QUESTIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO THE BID DATE.
2. ALL WORK SHALL BE IN ACCORDANCE WITH THE KENTUCKY BUILDING CODE; KENTUCKY STATE PLUMBING CODE; AND OTHER LOCAL, STATE, AND NATIONAL BUILDING CODES.
3. ACCESSIBLE PLUMBING FIXTURES SHALL BE INSTALLED PER THE KENTUCKY BUILDING CODE IN ACCORDANCE WITH ICC/ANSI 117.1 LATEST EDITION.
4. SEE SPECIFICATIONS FOR PIPE INSULATION REQUIREMENTS.
5. THE CONTRACTOR SHALL OBTAIN, AT HIS EXPENSE, APPLICABLE PERMITS & "TAP-ON" FEES.
6. NEW CONNECTIONS TO UTILITIES SHALL BE COORDINATED WITH THE APPROPRIATE UTILITY COMPANIES.
7. THESE PLANS ARE SCHEMATIC IN NATURE AND INDICATE THE APPROXIMATE AND GENERAL LOCATION OF THE WORK. CONTRACTOR SHALL INSTALL WORK THROUGH COORDINATION WITH OTHER TRADES AND TO SUIT FIELD CONDITIONS.
8. ILLUSTRATED HORIZONTAL SANITARY SEWER DRAIN/WASTE PIPING SHALL BE INSTALLED BELOW FLOORS. HORIZONTAL WATER & VENT PIPING SHALL BE INSTALLED ABOVE CEILINGS, UNLESS OTHERWISE NOTED.
9. UNLESS OTHERWISE NOTED, ALL PIPING SHALL BE CONCEALED IN WALLS OR CEILINGS.
10. COORDINATE ENTIRE PIPING LAYOUT WITH ALL OTHER TRADES TO ENSURE PROPER INSTALLATION AND REQUIRED CLEARANCES.
11. VERIFY EXACT LOCATION AND SIZE OF EXISTING SERVICES PRIOR TO MATERIAL ORDER OR INSTALLATION OF NEW PIPING.
12. VERIFY ALL DIMENSIONS BEFORE FABRICATION.
13. USE EXTREME CAUTION WHEN EXCAVATING. UNDERGROUND UTILITIES ILLUSTRATED ARE APPROXIMATE AND ARE SHOWN TO ALERT CONTRACTOR TO THEIR PRESENCE. CONTRACTOR MUST LOCATE/VERIFY UTILITIES BY HAND TOOL EXCAVATION.
14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DAMAGE THAT OCCURS TO EXISTING FACILITIES AND/OR NEW EQUIPMENT.
15. CONTRACTOR SHALL REPAIR/REPLACE ALL PAVEMENT, SIDEWALKS, LAWNS, ETC. DAMAGED IN THE COURSE OF CONSTRUCTION.
16. WHERE PIPING PASSES THROUGH FIRE RATED WALLS, FLOORS, OR CEILINGS; OPENINGS SHALL BE FIRE AND SMOKE STOPPED WITH AN U.L. APPROVED FIRE STOP SYSTEM AS MANUFACTURED BY 3M, DOW CORNING, OR APPROVED EQUAL.
17. PIPING MATERIALS SHALL BE LISTED EQUIVALENT GRADE OR BETTER. PVC PIPING SHALL NOT BE USED IN AIR PLENUMS OR THROUGH FIRE RATED ASSEMBLIES.

WATER INDOOR-	HARD COPPER PIPE
WATER OUTDOOR-	PVC
WATER UNDER CONCRETE SLAB-	SOFT COPPER TUBING
SEWER INDOOR-	PVC OR COPPER DWV
SEWER OUTDOOR-	PVC
GAS-	CARBON STEEL
STORM DRAIN INDOOR-	PVC
STORM DRAIN OUTDOOR-	PVC

18. DO NOT INSTALL PIPING DIRECTLY OVER ELECTRICAL PANELS. COORDINATE ROUTINGS WITH ELECTRICAL CONTRACTOR.
19. TO PROHIBIT MOVEMENT, SECURE FIXTURE WATER SUPPLY PIPES TO BUILDING STRUCTURE.
20. INSTALL HOSE BIBBS AND WALL HYDRANTS 18" ABOVE FINISHED FLOOR (U.N.O.). SECURE TO BUILDING STRUCTURE.
21. ALL OUTSIDE CLEANOUTS SHALL TERMINATE AT GRADE AND BE EMBEDDED IN CONCRETE. FINISHED 18"W x 18"L x 6"TK.
22. DIELECTRIC CONNECTIONS SHALL BE USED AT ALL DISSIMILAR MATERIAL PIPING JOINTS AND WHERE PIPE GOES THRU CONCRETE FLOOR SLAB ON GRADE.
23. FURNISH AND INSTALL PRESSURE RELIEF VALVES ON WATER HEATING EQUIPMENT. ROUTE DRAIN LINE PER KENTUCKY PLUMBING CODE TO NEAREST FLOOR DRAIN OR GRADE.
24. FABRICATE ARRESTORS FOR INDIVIDUAL FIXTURE SUPPLY LINES. ARRESTORS SHALL BE FABRICATED DURING "ROUGH-IN" WITH LINE SIZE PIPE, MINIMUM 6" LONG, AND PIPE CAP.
25. INSTALL GAS PIPING IN ACCORDANCE WITH THE NATIONAL FUEL GAS CODE NFPA 54.
26. PVC PIPING SHALL NOT BE USED THROUGH FIRE RATED ASSEMBLIES.
27. PLACE MILDEW RESISTANT SILICONE SEALANT AROUND ALL PLUMBING FIXTURES THAT CONTACT CASEWORK, FLOORS, WALLS, OR ANY OTHER HARD SURFACE.
28. INSTALL MANUFACTURED WATER HAMMER ARRESTORS ON ALL SUPPLY LINES TO QUICK ACTING VALVES.
29. COORDINATE SANITARY SEWER PIPING WITH STRUCTURAL MEMBERS AS REQUIRED. SEE ARCHITECTURAL AND STRUCTURAL DRAWINGS FOR MORE INFORMATION. REFER TO ARCHITECTURAL DRAWINGS FOR ALL PLUMBING FIXTURE LOCATIONS.
30. PIPE SUPPORTS SHALL BE INSTALLED FOR SEISMIC DESIGN CATEGORY 'D' AS SPECIFIED IN THE KENTUCKY BUILDING CODE.

TEMPERATURE MAINTENANCE CABLE NOTES

1. ALL DOMESTIC HOT WATER LINES SHALL RECEIVE TEMPERATURE MAINTENANCE CABLE BY ELECTRICAL CONTRACTOR. ALL LINES SHALL BE TRACED FROM POINT OF CONNECTION OF WATER HEATER TO WITHIN (10) LINEAR FEET OF EACH PLUMBING FIXTURE STOP VALVE. PLUMBING CONTRACTOR SHALL INSTALL LINES FOR ACCESSIBILITY TO THIS POINT. COORDINATE INSTALLATION WITH ELECTRICAL CONTRACTOR AND INSULATION CONTRACTOR.
2. 110° HOT WATER SYSTEMS

   UL-LISTED ELECTRIC SELF-REGULATING HEATING CABLE SYSTEM WITH COMPONENTS FOR MAINTAINING DOMESTIC HOT WATER TEMPERATURE WILL BE INSTALLED BY THE ELECTRICAL CONTRACTOR. THIS SYSTEM SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS. PLUMBER SHALL VERIFY CONTROLLERS ARE SET TO MAINTAIN 110° F WATER.

WATER HEATER SCHEDULE

MARK	MFG.	MODEL	TYPE	DIMENSIONS DIAMETER (IN.)	DIMENSIONS HEIGHT (IN.)	SERVICE OR LOCATION	TEMP. SETTING (DEG. F)	TEMP. RISE	RECOVERY (GPH)	RECOVERY (GPM)	STORAGE CAPACITY (GALLONS)	NATURAL GAS INPUT (BTU/H)	NATURAL GAS OUTPUT (BTU/H)	NATURAL GAS THERMAL EFF.	VOLTAGE/PHASE (V/PH)	REMARKS AND ACCESSORIES
WH-1	LOCHINVAR	LTN030 35	STORAGE	16	61.5	MECHANICAL 1112	110	70	36	–	30	35,000	33,600	96%	120/1	ALL

REMARKS AND ACCESSORIES:

A. DIRECT VENTING (SEALED COMBUSTION) REQUIRED
B. FURNISH WITH CONCENTRIC VENT KIT; SEE DRAWINGS FOR CONFIGURATION REQUIRED
C. SEISMICALLY RESTRAIN WATER HEATER TO ACCEPTABLE SUBSTRATE(S)

WATER HEATER SCHEDULE - ALTERNATE

MARK	MFG.	MODEL	TYPE	SERVICE OR LOCATION	TEMP. SETTING (DEG. F)	TEMP. RISE	RECOVERY (GPH)	RECOVERY (GPM)	STORAGE CAPACITY (GALLONS)	NATURAL GAS INPUT (BTU/H)	NATURAL GAS OUTPUT (BTU/H)	NATURAL GAS THERMAL EFF.	VOLTAGE/PHASE (V/PH)	REMARKS AND ACCESSORIES
WH-1	RHEEM	RTGH-950VN	INSTANTANEOUS	MECHANICAL 1112	105	45	–	8.4	NONE	199,900	187,906	94%	120/1	ALL

REMARKS AND ACCESSORIES:

A. DIRECT VENTING (SEALED COMBUSTION) REQUIRED
B. FURNISH WITH CONCENTRIC VENT KIT; SEE DRAWINGS FOR CONFIGURATION REQUIRED
C. THIS UNIT SHALL BE FURNISHED AS AN ALTERNATE; REFERENCE ARCHITECTURAL DRAWINGS FOR APPROPRIATE NUMBER

MARCUM ENGINEERING, LLC
500 SOUTH 17th STREET - PADUCAH, KENTUCKY 42002-0120
PHONE - 270.444.9274 FAX - 270.443.1904
www.marcumengineering.net

COPYRIGHT © 2012 - MARCUM ENGINEERING, LLC

STATE OF KENTUCKY
BACCUS L OLIVER 19897
LICENSED PROFESSIONAL ENGINEER

Hastings+Chivetta
ARCHITECTURE • PLANNING • ENGINEERING
625 Emerson | Suite 200 | Saint Louis, Missouri 63141 | Tel 314.983.2727 | Fax 314.983.2823 | www.hastingschivetta.com
CIVIL: BACON, FARMER, WORKMAN ENGINEERING & TESTING, INC., 1215 DUGUID DRIVE, MURRAY, KENTUCKY 42071
STRUCTURAL: BACON, FARMER, WORKMAN ENGINEERING & TESTING, INC., 403 N. COURT ST., MARION, ILLINOIS 62959
MPE: MARCUM ENGINEERING, LLC, 500 SOUTH 17TH STREET, PADUCAH, KENTUCKY, 42002

©Copyright 2012 Hastings+Chivetta Architects, Inc. Any reproduction or unauthorized use of this document or any part of this document without the express written consent of Hastings+Chivetta Architects, Inc. is prohibited.

MURRAY STATE UNIVERSITY
FACILITIES DESIGN AND CONSTRUCTION
DEPARTMENT FOR FACILITIES MANAGEMENT
615 GILBERT GRAVES DRIVE, MURRAY, KY 42071-3354

SPORTS PRACTICE FACILITY
MURRAY STATE UNIVERSITY
MURRAY, KENTUCKY
BID SET - 2012-01-04

MURRAY STATE UNIVERSITY

REVISIONS

Date -	2012-01-04
H+C Project No -	2983.00
FDC Project No -	10-007
BFW Project No -	11194
Marcum Project No -	11557

Sheet Name - PLUMBING LEAD SHEET

P1.00